

**COURTHOUSE LIMESTONE RETAINING WALL
RESTORATION PROJECT
EAST, SOUTH AND WEST SIDES OF COURTHOUSE SQUARE**

- 1) Remove the existing limestone blocks, reserving them to be put back in place.
- 2) Install a new concrete footing at the base
- 3) Replace the cylinder sockets for the flag poles with a water tight product
- 4) Clean the existing limestone blocks
- 5) Put back in place the cleaned limestone blocks
- 6) Return, level and pack dirt behind the restored retaining wall
(Richardson County will contract with Scholl Lawn and Landscape for the reseeding)
- 7) Return and level the dirt between the sidewalk and retaining wall
- 8) Project must be completed by July 31, 2022
- 9) Proof of insurance must be included with the bid notice and Richardson County must be named as an additional insured when bid is awarded and certificate must be delivered to the Richardson County Clerk before beginning project

Successful bidder must confer with the Richardson County Board of Commissioners with any modifications, changes or problems that occur during the restoration project to determine the solution. Any change orders in the project need to be approved by the Richardson County Board of Commissioners.